	Bottom Slab		1	107.50	1.00	0.15	16.13		
	Side Wall		2	107.50	0.15	0.60	19.35		
	Mani House to Pampa Mahakavi road R/s								
	Bottom Slab		1	107.50	1.00	0.15	16.13		
	Side Wall		2	107.50	0.15	0.60	19.35		
							70.96	4846.32	**343871.00**
	Basic Rate	4572.00							
	Area Weightage @ 6%	274.32							
	Total	**4846.32**							
4	KSRB 4.9.2: providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 **Page No. 19/ Item No. 4.46/ PWD SR 2012-13**	q			kg/Cum				
	55 kg/Cum		**70.96**		55.00		3902.53		
							39.00	7187.86	**280327.00**
	Basic Rate	6781.00							
	Area Weightage @ 6%	406.86							
	Total	**7187.86**							
5	KSRB 4-6.5: Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 **Page No. 17/ Item No. 4.32/ PWD SR 2012-13**	Sqm							
	Sides		2x2	107.50		0.90	387.00		
			2x2	107.50		0.90	387.00		
							774.00	298.92	**231364.00**
	Basic Rate	282.00							
	Area Weightage 6%	16.92							
	Total	**298.92**							
6	Supplying and fixing precast rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials.	Sqm							
			1	107.50	0.90		96.75		
			1	107.50	0.90		96.75		
	Data Rate Approved by CE Rs. 1600						**193.50**	1600.00	**309600.00**